BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

Negotiation Schedule - B

NAME OF WORK: Contruction of CC drain Marmma devi temple surrounding via phoenix school surroundings and other cross roads in Bagalagunte ward no 14

Sl. No	Description of work	Unit	Qty	Negotiation Rates Quoted by Contractor Sri M N RAMAIAH	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	642.4	142.62	Rupees One Hundred Forty Two and Sixty Two Paise Only
2	KSRB 2-2 : Earthwork excavation by for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.No. KBS 2.1 (b) / 2.3.5	Cum	295	196.38	Rupees One Hundred Ninety Six and Thirty Eight Paise Only
3	KSRB 4-1.3 : Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2	Cum	96.36	5597.40	Rupees Five Thousand Five Hundred Ninety Seven and Forty Paise Only
4	KSRB 4-1.6 : Providing and laying in position plain cement concrete of mix M20 with OPC @ 300kgs, with 20mm and down size graded granite metal coarseaggregates @ 0.69 cum and fine aggregtes @ 0.43 cum, machine mixed, concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation, plinth and cills, including cost of materials, labour, HOM of machinery, curing complete as per specifications. Specification NO. KBS 4.1, 4.2PWD SR 2018-19 P.No-13, It No 4.5	Cum	262.8	5845.35	Rupees Five Thousand Eight Hundred Forty Five and Thirty Four Paise Only

M N Ramaiah

Signature of the Contractor

Executive Engineer
Dasaahalli Division
BBMP

Scanned by CamScanner

5	KSRRB M2200-6. Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specificationsMORTH Specification No.1600 & 2200 [P. no.229 - l. no.28.8.2] PWD SR 18-19	Tonne	1971	77856.80	Rupees Seventy Seven Thousand Eight Hundred Fifty Six and Seventy Nine Paise Only
6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting,propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses,plinth cills and string courses cost of all materials, labour complete as per specifications.	Sqm	2336	392.76	Rupees Three Hundred Ninety Two and Seventy Six Paise Only
7	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortor including form work, lift charges , curing and concrtee finished surface on both sides etc, and complete as per the directions of Enginner in charges. (Data Rate)	Sqm	525.6	1671.53	Rupees One Thousand Six Hundred Seventy One and Fifty Two Paise Only
8	KSRRB M100-1 Loading and Unloading of Stone Boulder l Stone aggregates /Sand/ Kanker l Moorum.KSRRB M100-1: Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100/ Chapter 1	Cum	642.4	62.53	Rupees Sixty Two and Fifty Three Paise Only

M N. Ramesh.

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner